13

42

BRUHAT BANGALORE MAHANAGARA PALIKE						
Office of the Executive Engineer(Ele), Dasarahalli Zone, Hesaragatta main Road, Bangalore						
Tender Notification No:EE/ELE/DZ/TN/GN/02 /2012-13 Date: 16-08-2012						
Item No. 13						
SCHEDULE -B						
Name of Work:Providing Energy Saving equipments and connected accessories to High masts installation at ward no-15						
Name Of The Firm :				M/S Chowdeshwari Electricals		
Sl. No.	Description of work	Unit	Approved Qty	Approved Rates	Approved Rates in words	Amount
1	Supply and fixing of 4 pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc. complete. D) Rating: 100-125 Amps make : Group A	Each	4.00	7450.00	Rupees Seven Thousand Four Hundred Fifty Only	29800.00
2	Fabricating supplying and mounting MS box made out... SWG suitable for floor/wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer pain and finally finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete. a) 14 SWG	Sqcm	65000.00	0.37	Thirty Seven Paise Only	24050.00
3	Supplying and fixing angle iron frame work fabricated out of M.S angle iron... and M.S. flat... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. A).40x40x6mm.	P/Mtr	8.00	240.00	Rupees Two Hundred Forty Only	1920.00
4	Wiring for lighting/power circuit using one of PVC insulated 1100V grade, multi strands and copper conductor single core cable in open or consealed system of wiring. Make: Group A g. 16 sqmm	P/Mtr	8.00	140.00	Rupees One Hundred Forty Only	1120.00
5	Supplying and fixing of Miniature circuit breakers/on existing MCB distribution boards using necessary fixing materials and C Type Curve, indicator ON/OFF, energy cross 3 with short circuit breaking capacity of 10K and Complete wiring as required. Class A. make : (L&T, Siemens, MG, Legrand, ABB f).40-63Amps TPN 1) Group 'A'	Each	4.00	1495.00	Rupees One Thousand Four Hundred Ninety Five Only	5980.00

6	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanised, steel wire/steel tap armoured cable with PVC outer sheathing 1.1 KV class e) 3.5 core 25 sqmm	P/Mtr	130.00	**215.00**	**Rupees Two Hundred Fifteen Only**	**27950.00**
7	Labour charges for laying of 1.1KV class UG calbe when supplied agency in existing trench GI pipe/ stpnewre pip / on wall / on pole as required.II. On wall /Structure b.25 sqmm to 75 sqmm	P/Mtr	130.00	**11.00**	**Rupees Eleven Only**	**1430.00**
8	Digging of trench of 0.6m deep x 0.50 mtr wide refiling the trench to the required ground level and consolidating etc., Complete. (As per Civil SR KSRB 1-2, P-7).a. In soil (ordinary)	P/Mtr	115.00	**40.00**	**Rupees Forty Only**	**4600.00**
9	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes. b) 2.5 sqmm	Each	35.00	**7.50**	**Rupees Seven and Fifty Paise Only**	**262.50**
	f) 16 sqmm	Each	20.00	**14.00**	**Rupees Fourteen Only**	**280.00**
10	Supplying and drawing PVC flexible unarmoured copper control cable of approved make.E) 8c x 2.5Sqmm.1 Group A	P/Mtr	50.00	**316.00**	**Rupees Three Hundred Sixteen Only**	**15800.00**
11	Supplying and fixing electro mechanical timer (without contactor) using necessary bolts, nuts and washers etc.,Group 'A'	Each	4.00	**4200.00**	**Rupees Four Thousand Two Hundred Only**	**16800.00**
	Percentage					
In Figures	**1% below**		**BELOW**			
In Words	**one percent below**		**BELOW**			

I am prepared to take up the above work at 01 **% above/below (In Words** one percent **) the rates quoted in the Schedule 'B'**

For Chowdeshwari Electricals

Proprietor

Signature of the Contractor

Executive Engineer(Ele)
Dasarahalli Zone
BBMP Bangalore-73